
COST SENSITIVITY OF PIXEL CABLES

3-FEBRUARY, 2000
CABLE FOCUS SESSION

E. ANDERSSEN, LBNL


CABLE PLANT OVERVIEW

- REMINDER OF WHAT WE'RE TALKING ABOUT
- Cable Plant Consists of Cable Types 1-5
- COST ESTIMATES PRIMARILY CONCERNED WITH TYPE III AND TYPE IV





CABLE PLANT PHYSICAL LAYOUT







BASIS FOR ESTIMATE

- Rough Order of Magnitude
 - STARTED WITH TRYING TO COUNT EVERYTHING
- LABOR ESTIMATES
 - ESTIMATE OF FTE'S REQUIRED TO COMPLETE DELIVERY OF FLEX
 - PATCH PANEL PROTOTYPE EFFORT
- VENDOR QUOTE
 - TWISTING, CUSTOM CABLE, TERMINATION AND CONNECTORS,
- COMPARISON TO OTS COMPONENTS
 - CONNECTORS MATCH PRETTY WELL WITH LABOR AND PART COST
 - WIRE IS SOMEWHAT HIGH IN VENDOR QUOTE COMPARED TO OTS CABLE
- CURRENT ESTIMATE IS AN ORDER OF MAGNITUDE MORE THAN IS CURRENTLY IN CORE
 - EASY TO ACCOUNT FOR FACTOR ~5
 - Cable Length underestimated in initial assessment
 - VOLTAGE DROP STAYED THE SAME-DRIVING COST AS SQUARE OF LENGTH ERROR
 - POWER INCREASED



LABOR ESTIMATE

CONNECTORS

- FULL TERMINATION VARIES BETWEEN 1-3MINUTES PER PIN IN PRODUCTION, HAND TERMINATION ~ 1-3 \$/PIN
- THIS SEEMS TO ALSO BE PROPORTIONAL TO CONNECTOR COST WITHIN FACTOR 2

FLEX CABLE PRODUCTION

- PROCESS TUNED FOR 1.5 FTE's
- ~1.5 Man-days per exposure

Total Labor Proportional to Surface Area

- TYPE 1 POWER
 - 24K
- TYPE 2POWER
 - 124k
- MINTRACE FLEX-2PER BUNDLE
 - 62K
- HIGH VOLTAGE
 - 32K



PIXEL DETECTOR

VENDOR QUOTE

- GLENAIR
 - GENERALIZED CABLE BUNDLE TO MAX LENGTH, AND 7-WAY BUNDLE
 - ROM ESTIMATE OF COST/FT
 - PROBLEMS WITH IS41,
- CONNECTORS
 - MIL C ROUND
 - COST OF TERMINATION ≈ COST OF CONNECTOR
- NEED TO GET ANOTHER QUOTE FOR COMPARISON



COMPARISON WITH SCT

- Cost per Meter Breakdown.xls
- SUMMARY COST PER MODULE
 - SCT HAS INDIVIDUAL CABLES PER MODULE
 - Making an "Equivalent" cable using our quotes/estimates by Subtracting elements from our estimate is possible
 - COST OF SCT CABLE/METER IS WITHIN FACTOR 2 OF OUR COST/METER (1.7)

DIFFERENCES

- POWER
 - WE HAVE 3 PRIMARY VOLTAGES THEY HAVE 2
 - THEY HAVE CHOSEN A LARGER VOLTAGE DROP (SMALLER CONDUCTOR)
- CONTROL
 - WE HAVE ~60% MORE CONTROL PAIRS
 - THEY HAVE DISPENSED WITH RETURN LINES FOR MOST OF THEIR CONTROL LINES
- HIGH VOLTAGE
 - 500V SPEC IS NORMAL, WE HAVE 1000V WHICH IS MORE EXPENSIVE



SENSITIVITY

- GLENAIR COST SUMMARY.XLS
- LENGTH-VARIES BETWEEN 20-40KCHF/M
 - ERRORS IN LENGTH ESTIMATES
 - TYPE IV ~ 1 OM
 - TYPE III ~5M
 - Possibility to us US15
 - COULD SAVE 10-15M
- SENSE
 - CLEAR CUT
- INDIVIDUAL RETURNS
 - DIFFICULT TO KNOW HOW DEEP TO CUT, BUT COST IS LINEAR
- VOLTAGE DROP
 - DIFFICULT TO ASSESS
 - COST SAVINGS OFFSET BY NEED FOR OTHER ELECTRONICS
- MATERIALS
 - DIFFICULT TO UNDERSTAND

